



Addendum No. 2

Project: The Village @ West Jefferson
Louisville, Kentucky

Proj. No: 1583.01

Date: January 11, 2018

This addendum is a part of the bid documents. Acknowledge receipt on the Proposal Form.

Drawings

1. S-001: Pre-fabricated Wood Floor & Roof Truss Notes

Replace Note #10 with the following:

10. Maximum allowable truss Total Load Deflection shall not exceed the span length/360 (L/360). Maximum allowable truss Live Load Deflection shall not exceed the span length/360 (L/360) or 0.75 inches whichever is less.

2. S-203 & S-204: Various Details of Joist Hangers

The welding requirements for the joist hangers to the steel beam shall be a 1/4" fillet weld, 1-1/2" long on each end of the top flange of the hanger. These hanger may be field located and welded after beam is in place to simplify coordination with the truss locations.

Joist hangers to have gray primer, not galvanized.

3. M-102: Mini-Split System Equipment Schedule

Add the following as acceptable equipment manufacturer's: **York**

4. M-102: Packaged Heat Pump Roof Top Unit Schedule

Add the following as acceptable equipment manufacturer's: **York**

Prepared by,

Hal E. Kovert, AIA
Principal

file: 1583.01/E-1

Total Pages: (1) One

End of Addendum No. 2

